



Image

02-27-04

Express Mail" Mailing Label No. EL244341940US

+763

B

IN THE UNITED STATES PATENT AND TRADEMARK OFFICE

Applicant: Yoram Uziel et al.)
Application No. 09/721,167)
Filed: November 22, 2000) Group Art Unit: 1763
For: IN SITU MODULE FOR PARTICLE)
REMOVAL FROM SOLID-STATE)
SURFACES)
Examiner: Parviz Hassanzadeh) Attorney Docket No. STC-38090

TRANSMITTAL OF PRIORITY DOCUMENT

Commissioner for Patents
P.O. Box 1450
Alexandria, VA 22313-1450

Sir:

As required by 35 U.S.C. 119(b), transmitted herewith for filing in the above-identified application is a certified copy of PCT/IL99/00701, filed 12/23/1999.

Respectfully submitted,

February 26, 2004

By Talivaldis Cepuritis
Talivaldis Cepuritis (Reg. No. 20,818)

OLSON & HIERL, LTD.
20 North Wacker Drive
36th Floor
Chicago, Illinois 60606
(312) 580-1180



מדינת ישראל
STATE OF ISRAEL

Ministry of Justice
Patent Office

משרד המשפטים
לשכת הפטנטים

This is to certify that
annexed hereto is a true
copy of the documents as
originally deposited with
the patent application
particulars of which are
specified on the first page
of the annex.

זאת לתעודה כי
רצופים בזה העתקים
נכונים של המסמכים
שהופקדו לכתחילה
עם הבקשה לפטנט
לפי הפרטים הרשומים
בעמוד הראשון של
הנספח.

היום 21-12-2003
This
מ. לפרג
ממונה על הבוהנים
רשם הפטנטים
Commissioner of Patents

נתאשר
Certified

PCT

REQUEST

The undersigned requests that the present international application be processed according to the Patent Cooperation Treaty.

For receiving Office use only

International Application No. **PCT/IL 99 / 00701**

(23.12.99)

International Filing Date **23 DECEMBER 1999**

ISRAEL PATENT OFFICE

Name of receiving Office and "PCT International Application"

Applicant's or agent's file reference
(if desired) (12 characters maximum) **36511**

Box No. I TITLE OF INVENTION

LOCAL VECTORIAL PARTICLE CLEANING

Box No. II APPLICANT

Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)

ORAMIR SEMICONDUCTOR EQUIPMENT LTD.
P.O. Box 306
Yokneam 20692
Israel

☐ This person is also inventor.

Telephone No.

Facsimile No.

Teleprinter No.

State (that is, country) of nationality:

IL

State (that is, country) of residence:

IL

This person is applicant
for the purposes of:☐all designated
States☒all designated States except
the United States of America☐the United States
of America only☐the States indicated in
the Supplemental Box

Box No. III FURTHER APPLICANT(S) AND/OR (FURTHER) INVENTOR(S)

Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)

UZIEL, Yoram
Yodfat
D.N. Misgav 20180
Israel

This person is:

☐

applicant only

☒

applicant and inventor

☐inventor only (If this check-box
is marked, do not fill in below.)

State (that is, country) of nationality:

IL

State (that is, country) of residence:

IL

This person is applicant
for the purposes of:☐all designated
States☐all designated States except
the United States of America☒the United States
of America only☐the States indicated in
the Supplemental Box☒

Further applicants and/or (further) inventors are indicated on a continuation sheet.

Box No. IV AGENT OR COMMON REPRESENTATIVE; OR ADDRESS FOR CORRESPONDENCE

The person identified below is hereby/has been appointed to act on behalf of the applicant(s) before the competent International Authorities as:

☒

agent

☐

common representative

Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country.)

SANFORD T. COLB & CO.
Sanford T. Colb, Susie Dym, Eitan Shaulsky,
David Klein, Gershon Metzger, Daniel Kligler,
Daniel Feigelson and Hershel Ginsburg
P.O. Box 2273, Rehovot 76122, ISRAEL

Telephone No.

0972-8-9455122

Facsimile No.

0972-8-9454556

Teleprinter No.

☐ Address for correspondence: Mark this check-box where no agent or common representative is/has been appointed and the space above is used instead to indicate a special address to which correspondence should be sent.

Continuation of Box No. III FURTHER APPLICANT(S) AND/OR (FURTHER) INVENTOR(S)

If none of the following sub-boxes is used, this sheet should not be included in the request.

Name and address: (Family name followed by given name: for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)

LEVINSOHN, Natalie
10 Hatmarim Street
Hadera 38485
Israel

This person is:

- ☐ applicant only
☒ applicant and inventor
☐ inventor only (If this check-box is marked, do not fill in below.)

State (that is, country) of nationality:

IL [and ZA] ⁴⁴

State (that is, country) of residence:

IL

This person is applicant for the purposes of:

☐

all designated States

☐

all designated States except the United States of America

☒

the United States of America only

☐

the States indicated in the Supplemental Box

Name and address: (Family name followed by given name: for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)

YOGEV, David
44/6 Ha'alon
Nesher
Haifa 35811
Israel

This person is:

- ☐ applicant only
☒ applicant and inventor
☐ inventor only (If this check-box is marked, do not fill in below.)

State (that is, country) of nationality:

IL

State (that is, country) of residence:

IL

This person is applicant for the purposes of:

☐

all designated States

☐

all designated States except the United States of America

☒

the United States of America only

☐

the States indicated in the Supplemental Box

Name and address: (Family name followed by given name: for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)

ELISHA, Yehuda
4 Ya'ara Street
Kfar Vradim 25147
Israel

This person is:

- ☐ applicant only
☒ applicant and inventor
☐ inventor only (If this check-box is marked, do not fill in below.)

State (that is, country) of nationality:

IL

State (that is, country) of residence:

IL

This person is applicant for the purposes of:

☐

all designated States

☐

all designated States except the United States of America

☒

the United States of America only

☐

the States indicated in the Supplemental Box

Name and address: (Family name followed by given name: for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)

OFER, Yitzhak
14 Ha'horesh Street
Kiriati Tivon 36051
Israel

This person is:

- ☐ applicant only
☒ applicant and inventor
☐ inventor only (If this check-box is marked, do not fill in below.)

State (that is, country) of nationality:

IL

State (that is, country) of residence:

IL

This person is applicant for the purposes of:

☐

all designated States

☐

all designated States except the United States of America

☒

the United States of America only

☐

the States indicated in the Supplemental Box

☒ Further applicants and/or (further) inventors are indicated on another continuation sheet.

44 Deleted by RO

4 RO

Continuation of Box No. III FURTHER APPLICANT(S) AND/OR (FURTHER) INVENTOR(S)	
<i>If none of the following sub-boxes is used, this sheet should not be included in the request.</i>	
<p>Name and address: (Family name followed by given name: for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)</p> <p>FRISMAN, Lev 17/7 Derech Sara Street Zichron Ya'akov 30900 Israel</p>	<p>This person is:</p> <p><input type="checkbox"/> applicant only</p> <p><input checked="" type="checkbox"/> applicant and inventor</p> <p><input type="checkbox"/> inventor only (If this check-box is marked, do not fill in below.)</p>
State (that is, country) of nationality: <div style="text-align: center;">IL</div>	State (that is, country) of residence: <div style="text-align: center;">IL</div>
<p>This person is applicant for the purposes of: <input type="checkbox"/> all designated States <input type="checkbox"/> all designated States except the United States of America <input checked="" type="checkbox"/> the United States of America only <input type="checkbox"/> the States indicated in the Supplemental Box</p>	
<p>Name and address: (Family name followed by given name: for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)</p> <p>BARON, Jonathan 14 Nurit Street Haifa 34654 Israel</p>	<p>This person is:</p> <p><input type="checkbox"/> applicant only</p> <p><input checked="" type="checkbox"/> applicant and inventor</p> <p><input type="checkbox"/> inventor only (If this check-box is marked, do not fill in below.)</p>
State (that is, country) of nationality: <div style="text-align: center;">IL</div>	State (that is, country) of residence: <div style="text-align: center;">IL</div>
<p>This person is applicant for the purposes of: <input type="checkbox"/> all designated States <input type="checkbox"/> all designated States except the United States of America <input checked="" type="checkbox"/> the United States of America only <input type="checkbox"/> the States indicated in the Supplemental Box</p>	
<p>Name and address: (Family name followed by given name: for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)</p>	<p>This person is:</p> <p><input type="checkbox"/> applicant only</p> <p><input type="checkbox"/> applicant and inventor</p> <p><input type="checkbox"/> inventor only (If this check-box is marked, do not fill in below.)</p>
State (that is, country) of nationality:	State (that is, country) of residence:
<p>This person is applicant for the purposes of: <input type="checkbox"/> all designated States <input type="checkbox"/> all designated States except the United States of America <input type="checkbox"/> the United States of America only <input type="checkbox"/> the States indicated in the Supplemental Box</p>	
<p>Name and address: (Family name followed by given name: for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)</p>	<p>This person is:</p> <p><input type="checkbox"/> applicant only</p> <p><input type="checkbox"/> applicant and inventor</p> <p><input type="checkbox"/> inventor only (If this check-box is marked, do not fill in below.)</p>
State (that is, country) of nationality:	State (that is, country) of residence:
<p>This person is applicant for the purposes of: <input type="checkbox"/> all designated States <input type="checkbox"/> all designated States except the United States of America <input type="checkbox"/> the United States of America only <input type="checkbox"/> the States indicated in the Supplemental Box</p>	
<p>Name and address: (Family name followed by given name: for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)</p>	
<p>This person is:</p> <p><input type="checkbox"/> applicant only</p> <p><input type="checkbox"/> applicant and inventor</p> <p><input type="checkbox"/> inventor only (If this check-box is marked, do not fill in below.)</p>	
State (that is, country) of nationality:	State (that is, country) of residence:
<p>This person is applicant for the purposes of: <input type="checkbox"/> all designated States <input type="checkbox"/> all designated States except the United States of America <input type="checkbox"/> the United States of America only <input type="checkbox"/> the States indicated in the Supplemental Box</p>	
<p><input type="checkbox"/> Further applicants and/or (further) inventors are indicated on another continuation sheet.</p>	

Box No.V DESIGNATION OF STATES

The following designations are hereby made under Rule 4.9(a) (mark the applicable check-boxes; at least one must be marked):

Regional Patent

- ☒ AP ARIPO Patent: GH Ghana, GM Gambia, KE Kenya, LS Lesotho, MW Malawi, SD Sudan, SL Sierra Leone, SZ Swaziland, UG Uganda, ZW Zimbabwe, and any other State which is a Contracting State of the Harare Protocol and of the PCT
- ☒ EA Eurasian Patent: AM Armenia, AZ Azerbaijan, BY Belarus, KG Kyrgyzstan, KZ Kazakhstan, MD Republic of Moldova, RU Russian Federation, TJ Tajikistan, TM Turkmenistan, and any other State which is a Contracting State of the Eurasian Patent Convention and of the PCT
- ☒ EP European Patent: AT Austria, BE Belgium, CH and LI Switzerland and Liechtenstein, CY Cyprus, DE Germany, DK Denmark, ES Spain, FI Finland, FR France, GB United Kingdom, GR Greece, IE Ireland, IT Italy, LU Luxembourg, MC Monaco, NL Netherlands, PT Portugal, SE Sweden, and any other State which is a Contracting State of the European Patent Convention and of the PCT
- ☒ OA OAPI Patent: BF Burkina Faso, BJ Benin, CF Central African Republic, CG Congo, CI Côte d'Ivoire, CM Cameroon, GA Gabon, GN Guinea, GW Guinea-Bissau, ML Mali, MR Mauritania, NE Niger, SN Senegal, TD Chad, TG Togo, and any other State which is a member State of OAPI and a Contracting State of the PCT (if other kind of protection or treatment desired, specify on dotted line)

National Patent (if other kind of protection or treatment desired, specify on dotted line):

- | | |
|--|--|
| <input checked="" type="checkbox"/> AE United Arab Emirates | <input checked="" type="checkbox"/> LR Liberia |
| <input checked="" type="checkbox"/> AL Albania | <input checked="" type="checkbox"/> LS Lesotho |
| <input checked="" type="checkbox"/> AM Armenia | <input checked="" type="checkbox"/> LT Lithuania |
| <input checked="" type="checkbox"/> AT Austria and utility model | <input checked="" type="checkbox"/> LU Luxembourg |
| <input checked="" type="checkbox"/> AU Australia | <input checked="" type="checkbox"/> LV Latvia |
| <input checked="" type="checkbox"/> AZ Azerbaijan | <input checked="" type="checkbox"/> MD Republic of Moldova |
| <input checked="" type="checkbox"/> BA Bosnia and Herzegovina | <input checked="" type="checkbox"/> MG Madagascar |
| <input checked="" type="checkbox"/> BB Barbados | <input checked="" type="checkbox"/> MK The former Yugoslav Republic of Macedonia |
| <input checked="" type="checkbox"/> BG Bulgaria | |
| <input checked="" type="checkbox"/> BR Brazil | <input checked="" type="checkbox"/> MN Mongolia |
| <input checked="" type="checkbox"/> BY Belarus | <input checked="" type="checkbox"/> MW Malawi |
| <input checked="" type="checkbox"/> CA Canada | <input checked="" type="checkbox"/> MX Mexico |
| <input checked="" type="checkbox"/> CH and LI Switzerland and Liechtenstein | <input checked="" type="checkbox"/> NO Norway |
| <input checked="" type="checkbox"/> CN China | <input checked="" type="checkbox"/> NZ New Zealand |
| <input checked="" type="checkbox"/> CU Cuba | <input checked="" type="checkbox"/> PL Poland |
| <input checked="" type="checkbox"/> CZ Czech Republic and utility model | <input checked="" type="checkbox"/> PT Portugal |
| <input checked="" type="checkbox"/> DE Germany and utility model | <input checked="" type="checkbox"/> RO Romania |
| <input checked="" type="checkbox"/> DK Denmark and utility model | <input checked="" type="checkbox"/> RU Russian Federation |
| <input checked="" type="checkbox"/> EE Estonia and utility model | <input checked="" type="checkbox"/> SD Sudan |
| <input checked="" type="checkbox"/> ES Spain | <input checked="" type="checkbox"/> SE Sweden |
| <input checked="" type="checkbox"/> FI Finland and utility model | <input checked="" type="checkbox"/> SG Singapore |
| <input checked="" type="checkbox"/> GB United Kingdom | <input checked="" type="checkbox"/> SI Slovenia |
| <input checked="" type="checkbox"/> GD Grenada | <input checked="" type="checkbox"/> SK Slovakia and utility model |
| <input checked="" type="checkbox"/> GE Georgia | <input checked="" type="checkbox"/> SL Sierra Leone |
| <input checked="" type="checkbox"/> GH Ghana | <input checked="" type="checkbox"/> TJ Tajikistan |
| <input checked="" type="checkbox"/> GM Gambia | <input checked="" type="checkbox"/> TM Turkmenistan |
| <input checked="" type="checkbox"/> HR Croatia | <input checked="" type="checkbox"/> TR Turkey |
| <input checked="" type="checkbox"/> HU Hungary | <input checked="" type="checkbox"/> TT Trinidad and Tobago |
| <input checked="" type="checkbox"/> ID Indonesia | <input checked="" type="checkbox"/> UA Ukraine |
| <input checked="" type="checkbox"/> IL Israel | <input checked="" type="checkbox"/> UG Uganda |
| <input checked="" type="checkbox"/> IN India | <input checked="" type="checkbox"/> US United States of America |
| <input checked="" type="checkbox"/> IS Iceland | |
| <input checked="" type="checkbox"/> JP Japan | <input checked="" type="checkbox"/> UZ Uzbekistan |
| <input checked="" type="checkbox"/> KE Kenya | <input checked="" type="checkbox"/> VN Viet Nam |
| <input checked="" type="checkbox"/> KG Kyrgyzstan | <input checked="" type="checkbox"/> YU Yugoslavia |
| <input checked="" type="checkbox"/> KP Democratic People's Republic of Korea | <input checked="" type="checkbox"/> ZA South Africa |
| | <input checked="" type="checkbox"/> ZW Zimbabwe |
| <input checked="" type="checkbox"/> KR Republic of Korea | Check-boxes reserved for designating States which have become party to the PCT after issuance of this sheet: |
| <input checked="" type="checkbox"/> KZ Kazakhstan | <input checked="" type="checkbox"/> CR Costa Rica [x] MA Morocco |
| <input checked="" type="checkbox"/> LC Saint Lucia | <input checked="" type="checkbox"/> DM Dominica [x] TZ Tanzania |
| <input checked="" type="checkbox"/> LK Sri Lanka | |

Precautionary Designation Statement: In addition to the designations made above, the applicant also makes under Rule 4.9(b) all other designations which would be permitted under the PCT except any designation(s) indicated in the Supplemental Box as being excluded from the scope of this statement. The applicant declares that those additional designations are subject to confirmation and that any designation which is not confirmed before the expiration of 15 months from the priority date is to be regarded as withdrawn by the applicant at the expiration of that time limit. (Confirmation of a designation consists of the filing of a notice specifying that designation and the payment of the designation and confirmation fees. Confirmation must reach the receiving Office within the 15-month time limit.)

Box No. VI PRIORITY CLAIM

☐ Further priority claims are indicated in the Supplemental Box.

Filing date of earlier application (day/month/year)	Number of earlier application	Where earlier application is:		
		national application: country	regional application: regional Office	international application: receiving Office
item (1) 24 December, 1998 (24-12-98)	127720	IL		
item (2)				
item (3)				

☒ The receiving Office is requested to prepare and transmit to the International Bureau a certified copy of the earlier application(s) (only if the earlier application was filed with the Office which for the purposes of the present international application is the receiving Office) identified above as item(s):

* Where the earlier application is an ARIPO application, it is mandatory to indicate in the Supplemental Box at least one country party to the Paris Convention for the Protection of Industrial Property for which that earlier application was filed (Rule 4.10(b)(ii)). See Supplemental Box.

Box No. VII INTERNATIONAL SEARCHING AUTHORITY

Choice of International Searching Authority (ISA) (if two or more International Searching Authorities are competent to carry out the international search, indicate the Authority chosen; the two-letter code may be used):

ISA / US

Request to use results of earlier search; reference to that search (if an earlier search has been carried out by or requested from the International Searching Authority):

Date (day/month/year)

Number

Country (or regional Office)

Box No. VIII CHECK LIST: LANGUAGE OF FILING

This international application contains the following number of sheets:

request : 5
description (excluding
sequence listing part) : 11
claims : 5
abstract : 1
drawings : 3
sequence listing part
of description :
Total number of sheets : 25

This international application is accompanied by the item(s) marked below:

- ☒ fee calculation sheet
- ☐ separate signed power of attorney
- ☐ copy of general power of attorney; reference number, if any:
- ☐ statement explaining lack of signature
- ☐ priority document(s) identified in Box No. VI as item(s):
- ☐ translation of international application into (language):
- ☐ separate indications concerning deposited microorganism or other biological material
- ☐ nucleotide and/or amino acid sequence listing in computer readable form
- ☐ other (specify):

Figure of the drawings which
should accompany the abstract:

Language of filing of the
international application:

ENGLISH

Box No. IX SIGNATURE OF APPLICANT OR AGENT

Next to each signature, indicate the name of the person signing and the capacity in which the person signs (if such capacity is not obvious from reading the request).

Sanford T. Colb, Agent

For receiving Office use only

1. Date of actual receipt of the purported international application:	23 DECEMBER 1999 (23.12.99)	2. Drawings: <input checked="" type="checkbox"/> received: <input type="checkbox"/> not received:
3. Corrected date of actual receipt due to later but timely received papers or drawings completing the purported international application:		
4. Date of timely receipt of the required corrections under PCT Article 11(2):		
5. International Searching Authority (if two or more are competent): ISA / US	6. <input type="checkbox"/> Transmittal of search copy delayed until search fee is paid.	

For International Bureau use only

Date of receipt of the record copy
by the International Bureau:

PCT

FEE CALCULATION SHEET
Annex to the Request

For receiving Office use only

International application No.

PCT/IL 99 / 00701

23 DECEMBER 1999

Date stamp of the receiving Office

Applicant's or agent's
file reference

36511

Applicant

ORAMIR SEMICONDUCTOR EQUIPMENT LTD.

CALCULATION OF PRESCRIBED FEES

1. TRANSMITTAL FEE NIS426 T

2. SEARCH FEE USD700 S

International search to be carried out by UIS
(If two or more International Searching Authorities are competent in relation to the international application, indicate the name of the Authority which is chosen to carry out the international search.)

3. INTERNATIONAL FEE

Basic Fee

The international application contains 25 sheets.

first 30 sheets USD455 b1

remaining sheets x additional amount = b2

Add amounts entered at b1 and b2 and enter total at B USD455 B

Designation Fees

The international application contains ALL designations.

10 x USD105 = USD1050 D

number of designation fees payable (maximum 10) amount of designation fee

Add amounts entered at B and D and enter total at I USD1505 I

(Applicants from certain States are entitled to a reduction of 75% of the international fee. Where the applicant is (or all applicants are) so entitled, the total to be entered at I is 25% of the sum of the amounts entered at B and D.)

4. FEE FOR PRIORITY DOCUMENT (if applicable) P

5. TOTAL FEES PAYABLE NIS426+USD2205

Add amounts entered at T, S, I and P, and enter total in the TOTAL box

TOTAL

☐ The designation fees are not paid at this time.

MODE OF PAYMENT

☐ authorization to charge
deposit account (see below)

☐ cheque

☐ postal money order

☐ bank draft

☒ cash

☐ revenue stamps

☐ coupons

☐ other (specify):

DEPOSIT ACCOUNT AUTHORIZATION (this mode of payment may not be available at all receiving Offices)

The RO/ ☐ is hereby authorized to charge the total fees indicated above to my deposit account.

☐ (this check-box may be marked only if the conditions for deposit accounts of the receiving Office so permit) is hereby authorized to charge any deficiency or credit any overpayment in the total fees indicated above to my deposit account.

☐ is hereby authorized to charge the fee for preparation and transmittal of the priority document to the International Bureau of WIPO to my deposit account.

Deposit Account No.

Date (day/month/year)

Signature

ILS USD

426

700

455

455

1,050

1,505

75.8

501.8 2,205

LOCAL VECTORIAL PARTICLE CLEANING

FIELD OF THE INVENTION

The present invention relates generally to processing of semiconductor devices, and specifically to methods and apparatus for removal of foreign particles from semiconductor wafers and masks.

BACKGROUND OF THE INVENTION

Removal of contaminants from semiconductor wafers is a matter of great concern in integrated circuit manufacturing. As the critical dimensions of circuit features become ever smaller, the presence of even a minute foreign particle on the wafer during processing can cause a fatal defect in the circuit. Similar concerns affect other elements used in the manufacturing process, such as masks and reticles.

Various methods are known in the art for stripping and cleaning foreign matter from the surfaces of wafers and masks, while avoiding damage to the surface itself. For example, U.S. Patent 4,980,536, whose disclosure is incorporated herein by reference, describes a method and apparatus for removal of particles from solid-state surfaces by laser bombardment. U.S. Patents 5,099,557 and 5,024,968, whose disclosures are also incorporated herein by reference, describe a method and apparatus for removing surface contaminants from a substrate by high-energy irradiation. The substrate is irradiated by a laser with sufficient energy to release the particles while an inert gas flows across the wafer surface to carry away the released particles.

U.S. Patent 4,987,286, whose disclosure is likewise incorporated herein by reference, describes a method and apparatus for removing minute particles (as small as submicron) from a surface to which they are adhered. An energy transfer medium, typically a fluid, is interposed between each particle to be removed and the surface. The medium is irradiated with laser energy and absorbs sufficient energy to cause explosive evaporation, thereby dislodging the particles.

One particularly bothersome type of contamination that is found on semiconductor wafers is residues of photoresist left over from a preceding photolithography step. U.S. Patent 5,114,834, whose disclosure is incorporated herein by reference, describes a process and system for stripping this photoresist using a high-intensity pulsed laser. The laser beam is swept over the entire wafer surface so as to ablate the photoresist. The laser process can also be

effected in a reactive atmosphere, using gases such as oxygen, ozone, oxygen compounds, nitrogen trifluoride (NF₃), etc., to aid in the decomposition and removal of the photoresist.

Various methods are known in the art for localizing defects on patterned wafers. A summary of these methods is present in an article entitled "Defect Detection on Patterned Wafers," in *Semiconductor International* (May, 1997), pp. 64-70, which is incorporated herein by reference. There are many patents that describe methods and apparatus for defect localization, for example, U.S. Patents 5,264,912 and 4,628,531, whose disclosures are incorporated herein by reference. Foreign particles are one type of defects that can be detected using these methods.

U.S. Patent 5,023,424, whose disclosure is incorporated herein by reference, describes a method and apparatus using laser-induced shock waves to dislodge particles from a wafer surface. A particle detector is used to locate the positions of particles on the wafer surface. A laser beam is then focused at a point above the wafer surface near the position of each of the particles, in order to produce gas-borne shock waves with peak pressure gradients sufficient to dislodge and remove the particles. It is noted that the particles must be dislodged by the shock wave, rather than vaporized due to absorption of the laser radiation. U.S. Patent 5,023,424 further notes that immersion of the surface in a liquid (as in the above-mentioned U.S. Patent 4,987,286, for example) is unsuitable for use in removing small numbers of microscopic particles.

SUMMARY OF THE INVENTION

It is an object of the present invention to provide methods and apparatus for efficient removal of contaminants from solid-state surfaces, and particularly for removal of microscopic particles from semiconductor wafers and other elements used in semiconductor device production. The wafers may be bare, or they may have layers formed on their surface, whether patterned or unpatterned.

It is a further object of some aspects of the present invention to provide improved methods and apparatus for targeted removal of contaminant particles from a surface based on prior localization of the particles.

It is yet a further object of some aspects of the present invention to provide apparatus and methods for removal of particles from a surface with reduced probability that a particle, once removed, will settle back onto another area of the surface.

In preferred embodiments of the present invention, a substrate whose surface is to be cleaned, such as a semiconductor wafer, is mounted on a rotating chuck. A laser beam is scanned in a radial direction, between the center of the substrate and its periphery, thus defining a narrow, radial zone of irradiation. Any point on the substrate can be positioned in the zone simply by rotating the chuck. In this manner, the laser beam can reach substantially any or every point on the substrate surface by means of a simple one-dimensional scan, in cooperation with the chuck rotation. Preferably, gases having reactive properties and/or inert gases are flowed through the zone of irradiation in order to assist in ablating contaminants and in carrying particles away from the surface. The direction and characteristics of the gas flow are arranged so that the particles are carried away via the shortest possible path, thereby reducing the probability of their settling back onto the surface. The small dimensions of the irradiated zone are significant in shortening the particle removal path, as well as in reducing the quantity of gas necessary to achieve the desired effects.

In some preferred embodiments of the present invention, a particle localization system is used to determine coordinates of the particles that must be removed from the surface. These coordinates are preferably converted to polar coordinates, for use in driving the rotation of the chuck and scanning of the laser beam. The laser beam is directed to irradiate the surface at the locations indicated by the coordinates. Absorption of the laser beam energy at the surface, whether by the particles, the substrate or a material on the substrate, imparts sufficient energy to drive the particles off the surface substantially without damage to the surface itself. Optionally, a fluid or other energy transfer medium is applied to the surface, as described, for example, in the above-mentioned U.S. Patent 4,987,286, in order to promote removal of the particles by local explosive evaporation.

There is therefore provided, in accordance with a preferred embodiment of the present invention, a method for removing particles from the surface of a substrate, including:

- determining respective position coordinates of the particles on the surface; and
- directing a beam of electromagnetic energy at the coordinates of each of the particles in turn, such that absorption of the electromagnetic energy at the surface causes the particles to be dislodged from the surface substantially without damage to the surface itself.

Preferably, determining the position coordinates includes determining polar coordinates of the particles relative to a reference feature of the substrate. Most preferably, directing the

beam of electromagnetic energy includes rotating the substrate about an origin of the coordinates and scanning the beam in a radial direction with respect to the origin, responsive to the polar coordinates. Typically, determining the polar coordinates includes converting Cartesian coordinates of the particles determined by a particle detection system to the polar coordinates.

In a preferred embodiment, absorption of the electromagnetic energy causes ablation of the particles from the surface.

In another preferred embodiment, the method includes interposing an energy transfer medium between the particles to be removed and the surface, wherein absorption of the beam of electromagnetic energy causes local evaporation of the medium, thereby dislodging the particles.

In yet another preferred embodiment, the method includes flowing a gas, preferably a gas having reactive properties, in the vicinity of the surface, which gas cooperates with the absorbed energy in removing the dislodged particles from the surface.

Preferably, directing the beam of electromagnetic energy includes directing a laser beam at the surface, and the substrate includes a semiconductor wafer.

There is further provided, in accordance with a preferred embodiment of the present invention, apparatus for detecting and removing particles from the surface of a substrate, including:

a particle localization device, adapted to determine respective position coordinates of the particles on the surface; and

a particle removal device, coupled to receive the position coordinates from the particle localization device, and including an energy source which is configured to direct a beam of electromagnetic energy at the coordinates of each of the particles in turn, such that absorption of the electromagnetic energy at the surface causes the particles to be dislodged from the surface substantially without damage to the surface itself.

There is also provided, in accordance with a preferred embodiment of the present invention, apparatus for removing particles from the surface of a substrate, including:

a coordinate processor, adapted to receive input position coordinates of the particles on the surface and to determine, responsive to the input coordinates, output position coordinates for controlling the apparatus; and

an energy source, which is configured to direct a beam of electromagnetic energy at each of the particles in turn, responsive to the output position coordinates, such that absorption of the energy at the surface causes the particles to be dislodged from the surface substantially without damage to the surface itself.

5 Preferably, the output position coordinates include polar coordinates of the particles relative to a reference feature of the substrate. Further preferably, the apparatus includes a rotating chuck, which is configured to receive the substrate and to rotate the substrate about an origin of the polar coordinates so as to position each of the particles in turn under the beam of electromagnetic energy. Most preferably, the beam is scanned in a radial direction with respect
10 to the origin, responsive to the polar coordinates.

There is moreover provided, in accordance with a preferred embodiment of the present invention, apparatus for removing contaminants from the surface of a substrate, including:

a rotating chuck, which is configured to receive the substrate and to rotate the substrate about an axis of the chuck; and

15 an energy source which is configured to direct a beam of electromagnetic energy over the surface of the substrate, causing the contaminants to be dislodged from the surface, and to scan the beam in a radial direction with respect to the axis, in cooperation with the rotation of the chuck, so as to impinge upon substantially any point on the surface from which the contaminants are to be removed.

20 Preferably, the apparatus includes a chamber, which is configured to receive the substrate and to form an encapsulated region over a portion of the surface at which the beam of energy is directed. Further preferably, the chamber includes a window, forming one side of the encapsulated region, through which window the beam of energy passes to impinge upon the surface. Most preferably, the encapsulated region contains only a portion of the surface of the
25 substrate.

Preferably, the chamber includes one or more gas ports communicating with the encapsulated region so as to flow a gas therethrough, wherein the gas cooperates with the absorbed energy in removing the dislodged particles from the surface. Further preferably, the one or more gas ports include an inlet port for feeding a gas having reactive properties into the
30 encapsulated region and an outlet port for removing exhaust gas from the encapsulated region. Alternatively or additionally, the one or more gas ports include inlet and outlet ports through

which an inert gas is introduced into the chamber so as to generate a laminar flow of the gas over the surface of the substrate. Preferably, the gas flow through the encapsulated region carries away the contaminants dislodged from the surface, and wherein the gas ports are configured so that the gas flows in such a direction as to generally minimize a distance over which the contaminants must be carried before being removed from a vicinity of the surface.

There is additionally provided, in accordance with a preferred embodiment of the present invention, a method for removing contaminants from the surface of a substrate, including:

rotating the substrate about an axis thereof;

directing a beam of electromagnetic energy over the surface of the substrate, causing the contaminants to be dislodged from the surface; and

scanning the beam in a radial direction with respect to the axis, in cooperation with rotating the substrate, so that the beam impinges upon substantially any point on the surface from which the contaminants are to be removed.

The present invention will be more fully understood from the following detailed description of the preferred embodiments thereof, taken together with the drawings in which:

BRIEF DESCRIPTION OF THE DRAWINGS

Fig. 1 is a schematic illustration of a system for removal of particles from the surface of a semiconductor wafer, in accordance with a preferred embodiment of the present invention;

Fig. 2 is a schematic top view of a semiconductor wafer, illustrating a coordinate transformation applied with regard to particles on the wafer surface, in accordance with a preferred embodiment of the present invention;

Fig. 3 is a schematic top view of another type of semiconductor wafer, to which the coordinate transformation of Fig. 2 may be applied;

Fig. 4 is a schematic, sectional illustration of a semiconductor wafer in a particle removal process chamber, in accordance with a preferred embodiment of the present invention; and

Fig. 5 is a schematic top view of the wafer and process chamber shown in Fig. 4.

DETAILED DESCRIPTION OF PREFERRED EMBODIMENTS

Fig. 1 is a schematic view of a system 20 for location and removal of contaminants from a surface of a semiconductor wafer 26, in accordance with a preferred embodiment of the present invention. System 20 comprises two sub-systems: a particle localization device 22 and a particle removal device 24. Typically, devices 22 and 24 are separate entities, as shown in the figure. Localization device 22 determines the coordinates of contaminant particles 28 on the surface of the wafer. The coordinates are passed to a coordinate processor 34, which stores the coordinates and transforms them to a coordinate frame of particle removal device 24. The wafer is then transferred to the particle removal device, where the coordinates are used to direct the removal of the particles from the surface. Alternatively, devices 22 and 24 are constructed as a single, integral unit, which both determines the particle coordinates and removes the particles accordingly, without the need to transfer the wafer from one entity to the next.

Particle localization device 22 may comprise any suitable automated inspection system known in the art, such as the defect detection systems mentioned in the Background of the Invention. For example, the KLA-Tencor "Surfscan" system may be used for this purpose. Typically, a laser 30 irradiates the surface of wafer 26, and a detector 32 senses irregularities in the radiation reflected from the surface. The irregularities are analyzed to determine the coordinates of particles 28, and possibly of other surface defects, as well. Inspection systems known in the art generally determine Cartesian coordinates of such particles and other defects. Preferably, device 22 is capable of distinguishing between irregularities due to particles and due to other causes. Alternatively, device 24 may attempt (without success) to remove particles from locations of defects that are not removable particles. Aside from reducing the throughput of system 20, it is not likely that any harm will result to wafer 26 due to the processing of these non-particle defects by device 24.

Particle removal device 24 comprises a laser 36, which directs an intense beam of energy at the surface of wafer 26. In some preferred embodiments of the present invention, the laser comprises an excimer laser, such as a Lambda Physik LPX315 IMC laser, which emits ultraviolet radiation. Alternatively, other laser types and wavelengths, such as infrared or visible lasers, may be used. The wafer is contained in a chamber 38, which is described in detail hereinbelow. The laser energy is absorbed at the wafer surface, causing particles 28 to be

dislodged from the surface substantially without damage to the surface itself. Typically, absorption of the laser energy, by the particles and/or by the wafer, causes the particles to be ablated or otherwise dislodged from the surface, as described, for example, in the above-mentioned U.S. Patent 5,114,834 or in PCT patent application PCT/IL96/00141, which is also incorporated herein by reference. Additionally or alternatively, as described in the above-mentioned U.S. Patent 4,987,286, an energy transfer medium is applied to the surface. The laser energy, absorbed by the medium and/or by the wafer, causes explosive evaporation, thereby dislodging the particles. Further alternatively, device 24 may use any other suitable method of localized particle removal that is known in the art. Optionally, the wafer in the chamber is pre-heated, typically to a temperature of about 150-250°C, in order to facilitate removal of the particles when irradiated by the laser beam.

As another option, device 24 may comprise means for visual inspection of the wafer surface, such as a video camera with suitable optics and a video monitor (not shown in the figures). An operator of system 20 can observe the video monitor to inspect the locations of particles 28, both before and after particle removal.

Fig. 2 is a schematic top view of wafer 26, illustrating a coordinate transformation applied by coordinate processor 34, in accordance with a preferred embodiment of the present invention. As noted above, particle localization device 22 typically provides Cartesian coordinates of defects 28, as shown on the left side of the figure. The coordinate axes are referred to a reference mark on the wafer, such as a flat 42 on one side of the wafer. For each particle 28, processor 34 determines a radial coordinate r , corresponding to a radial distance of the particle location from a center point of the wafer, and an angular coordinate θ , relative to a reference axis determined by flat 42, as shown on the right side of the figure. The polar coordinates are used advantageously to drive movement of wafer 26 in chamber 38 and scanning of the beam of laser 36, as described hereinbelow.

Fig. 3 is a schematic top view of another wafer 46 having a notch 48, as is common in new-generation 300 mm wafers, in place of flat 42. The reference axis for determination of the angular coordinate θ of the defects is thus located relative to the notch. In other respects, however, wafer 46 may be used interchangeably with wafer 26 in the preferred embodiments described herein.

Reference is now made to Figs. 4 and 5, which schematically illustrate details of

chamber 38, in accordance with a preferred embodiment of the present invention. Fig. 4 is a sectional side view, and Fig. 5 is a top view. Chamber 38 comprises a rotating chuck 64, on which wafer 26 rests securely (typically by vacuum suction, as is known in the art), and an upper cover 50 over the surface that is to be cleaned. The laser beam irradiates the wafer surface through a window 62, preferably a quartz window of sufficient transparency at the laser wavelength. The window is preferably long and narrow, covering a full radius of wafer 26. To remove any one of particles 28, chuck 64 is rotated to an appropriate angle θ so that the particle is located under window 62, and the laser beam is scanned radially so that the particle is contained within a footprint 70 of the beam. When the laser is fired, the particle is ablated from the surface. If necessary, multiple laser pulses are applied at all or some of the particle locations, as may be required for complete particle removal.

The radial scanning of the laser beam can be accomplished either by angular deflection of the beam, using any sort of suitable optical scanner, or by translating an optical beam-handling assembly (or even the entire laser) over the wafer in a radial direction. These and other suitable methods of scanning will be apparent to those skilled in the art. In any case, no translational movement of wafer 26 is required for the laser beam to reach substantially any point on the wafer surface. The elimination of wafer translation allows chamber 38 to be made substantially smaller than chambers used in laser particle removal systems known in the art, which must have dimensions of at least twice the wafer diameter in order to accommodate full X-Y translation. Chamber 38, by contrast, must accommodate only wafer rotation.

Although system 20 is designed for the purpose of local particle removal, based on known particle coordinates, particle removal device 24 may also be used advantageously to scan and remove contaminants, such as photoresist residues, from the entire surface of wafer 26. In this case, the wafer is rotated in steps through the entire 360° of rotation of chuck 64, while at each step, laser footprint 70 is scanned over the entire radius of the wafer. Alternatively, a selected sector of the wafer may be cleaned in this manner.

Cover 50 and window 62 of chamber 38 define an encapsulated region 60 underneath the window. This is the region in which the laser beam acts on particles 28. Preferably, a process gas is fed into region 60 through a plurality of gas inlet ports 56. Most preferably, the process gas comprises a gas or a combination of gases having reactive properties, such as ozone, a nitrogen oxide (N_xO_y), NF_3 , or other oxygen- or fluorine-containing gases.

Ultraviolet laser radiation in region 60 causes these gases to release reactive oxygen and fluorine radicals, which aid in the decomposition of the particles and cleaning of the wafer surface. Because region 60 covers only a small part of the wafer surface, only a relatively small quantity of the process gas is needed to fill the region to a required partial pressure of the gas.

- 5 This reduction in process gas consumption, relative to reactive contaminant removal methods known in the art, results in cost savings and alleviates environmental concerns due to release of poisonous reactive gases from the chamber.

Alternatively, a vapor may be introduced through the ports, which condenses to form a liquid film on the surface. In this case, laser irradiation causes explosive local evaporation of
10 the liquid, driving the particles off the wafer surface.

The gas from region 60 is preferably exhausted through gas exhaust ports 58. As these ports are immediately adjacent to region 60, the particles removed from the wafer surface will generally be swept immediately out of the region and away from the wafer surface. By minimizing the distance that released particles must travel over the wafer surface, system 20
15 thus reduces the likelihood that a released particle will settle back down on another part of the wafer surface. Rapid and efficient removal of the released particles is very important, because when released particles do settle back down on the wafer, they may be even harder to remove than they were initially.

Additionally or alternatively to the flow of a process gas through ports 56 and 58, a
20 background gas, generally an inert gas or gas mixture, may be made to flow over the wafer surface. The background gas is preferably injected through one or more inlet ports 52 and flows over wafer 26 in a laminar layer, exiting through one or more outlet ports 54. This laminar gas flow effectively seals off the wafer surface to further contamination and eliminates the possibility of particles escaping from region 60 and settling on other areas of the wafer.
25 The position of ports 52 and 54 in Fig. 4 is such that the background gas will flow across the wafer surface in a direction perpendicular to the long axis of region 60. Alternatively, the ports may be positioned so that the gas will flow parallel to this axis, or in any other suitable direction across the wafer.

Although preferred embodiments are described herein with reference to removal of
30 particles from semiconductor wafers, the principles of the present invention may similarly be applied to removing contaminants from other sorts of substrates, as well. For example, the

apparatus and methods described herein are especially suited for cleaning photolithography masks, reticles and other elements used in semiconductor device processing. Furthermore, although in the preferred embodiments described above, a laser beam is used to remove the particles from the wafer surface, other types of electromagnetic energy beams may also be used
5 for this purpose.

It will thus be appreciated that the preferred embodiments described above are cited by way of example, and that the present invention is not limited to what has been particularly shown and described hereinabove. Rather, the scope of the present invention includes both combinations and subcombinations of the various features described hereinabove, as well as
10 variations and modifications thereof which would occur to persons skilled in the art upon reading the foregoing description and which are not disclosed in the prior art.

CLAIMS

1. A method for removing particles from the surface of a substrate, comprising:
determining respective position coordinates of the particles on the surface; and
directing a beam of electromagnetic energy at the coordinates of each of the particles in
5 turn, such that absorption of the electromagnetic energy at the surface causes the particles to be
dislodged from the surface substantially without damage to the surface itself.
2. A method according to claim 1, wherein determining the position coordinates comprises
determining polar coordinates of the particles relative to a reference feature of the substrate.
3. A method according to claim 2, wherein directing the beam of electromagnetic energy
10 comprises rotating the substrate about an origin of the coordinates and scanning the beam in a
radial direction with respect to the origin, responsive to the polar coordinates.
4. A method according to claim 2, wherein determining the polar coordinates comprises
converting Cartesian coordinates of the particles determined by a particle detection system to
the polar coordinates.
- 15 5. A method according to any of claims 1-4, wherein absorption of the electromagnetic
energy causes ablation of the particles from the surface.
6. A method according to any of claims 1-4, and comprising interposing an energy transfer
medium between the particles to be removed and the surface, wherein absorption of the beam
of electromagnetic energy causes local evaporation of the medium, thereby dislodging the
20 particles.
7. A method according to any of claims 1-4, and comprising flowing a gas in the vicinity of
the surface, which gas cooperates with the absorbed energy in removing the dislodged particles
from the surface.
8. A method according to claim 7, wherein flowing the gas comprises flowing a gas having
25 reactive properties.
9. A method according to any of claims 1-4, wherein directing the beam of
electromagnetic energy comprises directing a laser beam at the surface.
10. A method according to any of claims 1-4, wherein the substrate comprises a
semiconductor wafer.

11. Apparatus for detecting and removing particles from the surface of a substrate, comprising:

a particle localization device, adapted to determine respective position coordinates of the particles on the surface; and

5 a particle removal device, coupled to receive the position coordinates from the particle localization device, and comprising an energy source which is configured to direct a beam of electromagnetic energy at the coordinates of each of the particles in turn, such that absorption of the electromagnetic energy at the surface causes the particles to be dislodged from the surface substantially without damage to the surface itself.

10 12. Apparatus according to claim 11, wherein absorption of the electromagnetic energy causes ablation of the particles from the surface.

13. Apparatus according to claim 11, wherein an energy transfer medium is applied to the surface of the substrate in the particle removal device, and wherein absorption of the beam of electromagnetic energy at the surface causes local evaporation of the medium, thereby
15 dislodging the particles.

14. Apparatus according to any of claims 11-13, wherein the particle removal device comprises a coordinate processor, which is adapted to determine polar coordinates of the particles relative to a reference feature of the substrate, and wherein the particle removal device comprises a rotating chuck, on which the substrate is mounted, which rotates the substrate
20 responsive to the polar coordinates so as to position the particles under the beam.

15. Apparatus for removing particles from the surface of a substrate, comprising:

a coordinate processor, adapted to receive input position coordinates of the particles on the surface and to determine, responsive to the input coordinates, output position coordinates for controlling the apparatus; and

25 an energy source, which is configured to direct a beam of electromagnetic energy at each of the particles in turn, responsive to the output position coordinates, such that absorption of the energy at the surface causes the particles to be dislodged from the surface substantially without damage to the surface itself.

16. Apparatus according to claim 15, wherein the output position coordinates comprise
30 polar coordinates of the particles relative to a reference feature of the substrate.

17. Apparatus according to claim 16, and comprising a rotating chuck, which is configured to receive the substrate and to rotate the substrate about an origin of the polar coordinates so as to position each of the particles in turn under the beam of electromagnetic energy.

18. Apparatus according to claim 17, wherein the beam is scanned in a radial direction with respect to the origin, responsive to the polar coordinates.

19. Apparatus according to any of claims 15-18, and comprising a chamber, which is configured to receive the substrate and to form an encapsulated region over a portion of the surface at which the beam of energy is directed.

20. Apparatus according to claim 19, wherein the chamber comprises one or more gas ports communicating with the encapsulated region so as to flow a gas therethrough, wherein the gas cooperates with the absorbed energy in removing the dislodged particles from the surface.

21. Apparatus according to any of claims 15-18, wherein the energy source comprises a laser.

22. Apparatus according to any of claims 15-18, wherein the substrate comprises a semiconductor wafer.

23. Apparatus for removing contaminants from the surface of a substrate, comprising:
a rotating chuck, which is configured to receive the substrate and to rotate the substrate about an axis of the chuck; and

an energy source which is configured to direct a beam of electromagnetic energy over the surface of the substrate, causing the contaminants to be dislodged from the surface, and to scan the beam in a radial direction with respect to the axis, in cooperation with the rotation of the chuck, so as to impinge upon substantially any point on the surface from which the contaminants are to be removed.

24. Apparatus according to claim 23, and comprising a chamber, which is configured to receive the substrate and to form an encapsulated region over a portion of the surface at which the beam of energy is directed.

25. Apparatus according to claim 24, wherein the chamber comprises a window, forming one side of the encapsulated region, through which window the beam of energy passes to impinge upon the surface.

26. Apparatus according to claim 24, wherein the encapsulated region contains only a portion of the surface of the substrate.

27. Apparatus according to claim 24, wherein the chamber comprises one or more gas ports communicating with the encapsulated region so as to flow a gas therethrough, wherein the gas cooperates with the absorbed energy in removing the dislodged particles from the surface.

28. Apparatus according to claim 27, wherein the one or more gas ports comprise an inlet port for feeding a gas having reactive properties into the encapsulated region and an outlet port for removing exhaust gas from the encapsulated region.

29. Apparatus according to claim 27, wherein the one or more gas ports comprise inlet and outlet ports through which an inert gas is introduced into the chamber so as to generate a laminar flow of the gas over the surface of the substrate.

30. Apparatus according to claim 27, wherein the gas flow through the encapsulated region carries away the contaminants dislodged from the surface, and wherein the gas ports are configured so that the gas flows in such a direction as to generally minimize a distance over which the contaminants must be carried before being removed from a vicinity of the surface.

31. Apparatus according to any of claims 23-30, wherein the energy source comprises a laser.

32. Apparatus according to any of claims 23-30, wherein the substrate comprises a semiconductor wafer.

33. A method for removing contaminants from the surface of a substrate, comprising:
rotating the substrate about an axis thereof;
directing a beam of electromagnetic energy over the surface of the substrate, causing the contaminants to be dislodged from the surface; and
scanning the beam in a radial direction with respect to the axis, in cooperation with rotating the substrate, so that the beam impinges upon substantially any point on the surface from which the contaminants are to be removed.

34. A method according to claim 33, and comprising forming an encapsulated region over a portion of the surface at which the beam of energy is directed, wherein the encapsulated region contains only a portion of the surface of the substrate.

35. A method according to claim 34, and comprising flowing a gas through the encapsulated region, wherein the gas cooperates with the absorbed energy in removing the dislodged particles from the surface.

36. A method according to claim 35, wherein the gas flowing through the encapsulated region carries away the contaminants dislodged from the surface, and wherein flowing the gas comprises causing gas to flow in such a direction as to generally minimize a distance over which the contaminants must be carried before being removed from a vicinity of the surface.

37. A method according to any of claims 33-36, and comprising interposing an energy transfer medium between the contaminants and the surface, wherein directing the beam of electromagnetic energy causes local evaporation of the medium, thereby dislodging the contaminants.


ABSTRACT

A method for removing particles (28) from the surface of a substrate (26) includes determining respective position coordinates of the particles on the surface. A beam of electromagnetic energy is directed at the coordinates of each of the particles in turn, such that
5 absorption of the electromagnetic energy at the surface causes the particles to be dislodged from the surface substantially without damage to the surface itself.

1/3

20 →

FIG. 1



2/3

FIG. 2




FIG. 3

